



isoFlex PVC[®]

Submittal



Company Profile

iChemEG® was established in 2019 in Cairo, Egypt.

Team business with values that include: experience, do the right thing and work hard.

As the manufacturer, we verify that only the best products are shipped out to your project

We constantly test and review our systems for continuous innovation to provide you with the best solutions

Yeah, we're obsessed, but in a good way.

iChemEG® classified as a class A contractor and have built a strong reputation and growing business in Egypt

we are able to undertake multidisciplinary projects of scale and complexity

Fast growth in business and revenue is a testimony to our proven capability to deliver quality products and services with speed and cost effectiveness

Company Information

Registration Name : iChemEG

Establishment Year : Since 2019

Address : 22EI-Shaheed Mohamed Abd El-Hadi Street, Nasr City, Cairo, Egypt

Tel : +222909120

Office Mob : +201010027900 / 01010042900

Email : info@ichemeg.com

isoFlex PVC®



Description

The isoFlex PVC® a Supercast waterstops are extruded from a high grade PVC compound which has been formulated to give excellent flexibility and longevity characteristics. They are available as straight lengths and factory produced intersections or as a factory prefabricated segment of a network to minimize site jointing.

Key Features

Multi-rib selection, providing tortuous and impenetrable water checks Clips facilitate easy fixing. Material and cross-section allow extremely easy on site welding. iChem quality is in high strength polyvinyl chloride material.

- isoFlex PVC® is resistant to Seawater, Salt solution, Potable and Sewage water.
- Range of profiles to suit every need.
- Simple on-site jointing.
- Adheres to concrete.
- Versatile in use.
- Economical.

Uses

The isoFlex PVC® range of PVC waterstops is designed to provide an integral sealing system for movement and construction joints in concrete cast in-situ. These joints typically occur in the following types of structure:

Water retaining

- Reservoirs, water towers and sewage tanks.
- Dams, culverts, canals and spillways.
- Swimming pools.
- Bundled areas surrounding liquid retaining tanks.

Water excluding



Application Instructions

Welding: Waterstops are made from thermoplastic PVC and can therefore be welded. The ends are heated with welding equipment until the PVC gets plastic and then immediately pressed together.

isoFlex PVC® are allowing easy on site welding, including the prefabrication of cross, T, L and corner pieces.

A wide ranges of standardized junction pieces are available. All have a 30 cm free leg, allowing easy site welding to Waterbars. In case non-standardized junction pieces are required, drawing must be provided, giving exact details of angles.

Packing

Available in Rolls at 15 & 20 & 30 meter






Shelf Life

Open shelf life as long as it is stored away from heat and fires sources. .

Health and safety

As with all construction chemicals products caution should always be exercised. Protective clothing such as gloves and goggles should be worn. Treat any splashes to the skin or eyes with fresh water immediately. Should any of the products be accidentally swallowed, do not induce vomiting, but call for medical assistance immediately.

isoFlex PVC[®]

Centrally Profile					
Profile Type		Width(cm)	Roll Length(m)	Thickness-mm (10%)	Max. Water head(m)
		Construction Joint Profile			
Standard	V20	20	20	6	15
	V24	24	20	6	25
	V32	32	15	6	30
Light	V20-L	20	30	4	10
	V24-L	24	30	4	15
	V32-L	32	20	4	25
		Construction Joint Special Profile			
Standard	SV20	20	15	6	15
	SV24	24	15	6	25
	SV32	32	15	6	30
Light	SV20-L	20	15	4	10
	SV24-L	24	15	4	15
	SV32-L	32	15	4	25
		Expansion Joint Profile			
Standard	O20	20	15	6	15
	O24	25	15	6	25
	O32	32	15	6	30
Light	O20-L	20	15	4	10
	O24-L	25	15	4	15
	O32-L	32	15	4	25
Surface Profile					
Profile Type & Drawing		Width(cm)	Roll Length(m)	Thickness-mm (10%)	Max. Water head(m)
		Expansion Joint Profile			
Standard	OR25	25	15	4	10
	OR32	32	15	4	15
		Construction Joint Profile			
Light	R20	20	15	4	5
	R24	24	15	4	10
	R32	32	15	4	15

isoFlex PVC[®]



Profile Type	Details Drawing
<p>Construction Joint Profile</p>	
<p>Construction Joint Special Profile</p>	
<p>Expansion Joint Profile</p>	
<p>Expansion Joint Profile</p>	
<p>Construction Joint Profile</p>	



وزارة البحث العلمي والتكنولوجيا
معهد بحوث البترول المصري
Egyptian Petroleum Research Institute (EPRI)
مركز حماية الأسطح المعدنيه spc

تقرير فنى لعينة مطاط
الخاص بشركة (iChemEG)

تاريخ : 2023/7/19

العينة: قطاع من شريط مطاطى لونه أسود من مادة (isoFlex PVC)

السادة شركة (iChemEG)

لقد تمت الاختبارات لقطاع من شريط مطاطى لونه أسود من مادة (isoFlex PVC) طبقا للمواصفات القياسية العالمية وقد سجلت النتائج فى الجدول التالى


Test type	Results	Reference value	Standard	Remark
Tensile strength	14.58N/mm2	≥ 10 N/mm2	DIN 53455	Accept
Tear strength	14.61 N/mm	≥ 12 N/mm	DIN 53507 A	Accept
Shore A Hardness	95	90 ± 5	DIN 53505	Accept
Elongation at Break	312 %	> 300 %	DIN 53455	Accept

الخلاصة : العينة اجتازت الاختبارات السابقة بنجاح طبقا للمواصفات القياسية العالمية

استشارى المركز
أ.د. أسامه أبو العنين
(Signature)



مدير مركز حماية الأسطح
أ.د. أشرف السعيد
(Signature)



NATIONAL RESEARCH CENTRE
ENHR EL DOKKI, CAIRO, EGYPT
Central Unit For Analysis And
Scientific Services (CUASS)
Material Test Lab.

المركز القومي للبحوث

القاهرة - جمهورية مصر العربية
وحدات التحليل والخدمات العلمية المركزية
معمل اختبار المواد



This report was given to you representing only the results for the testing sample of iso Flex PVC waterproof Q30 . Delivered from ChemEG construction chemistry. These results and conclusions were given to you without any responsibility on THE CERAMICS, POLYMERS AND SOLID MATTER DEP. of THE MATERIAL TEST LAB in THE NATIONAL RESEARCH CENTRE for pick up the samples to be tested .


*Head of Director of The Board of Central Department
for Scientific Analysis and Tests*

SUPERVISOR

**OF CERAMICS, POLYMER AND
SOLID MATTER DEPARTMENT**

PROF. DR. MOSTAFA ZAKI MOSTAFA





NATIONAL RESEARCH CENTRE
TARIK St. DOKKI, CAIRO, EGYPT
Central Unit For Analysis And
Scientific Services (CUASS)
Material Test Lab.

المركز القومي للبحوث

القاهرة - جمهورية مصر العربية
وحدة التحليل والخدمات العلمية المركزية
معمل اختبار المواد




Tear strength test according to ASTM D624

on a sample of Iso Flex PVC waterproof O30

Delivered from iChemEG construction chemistry.

No.	Tear strength (N/cm)	Mean (N/cm)
1	16.45	17.44
2	17.31	
3	18.28	
4	17.65	
5	17.49	






NATIONAL RESEARCH CENTRE
TAHRAH St. DOKKI, CAIRO, EGYPT
Central Unit For Analysis And
Scientific Services (CUASS)
Material Test Lab.

المركز القومي للبحوث
القاهرة - جمهورية مصر العربية
وحدة التحليل والتحاليل الطيفية المركزية
معمل اختبار المواد



Test Report

Report No.	MOI 5449 04 2021
Client	iChemEG construction chemistry
Authority & date	Request Orders 20/4/2021
Items Tested	iso Flex PVC waterstops (30)
Results	The detailed test results are given on the following pages of this report (4 pages) .
Report Typist	* Mix. Nagaa Mohamed-Sara Abdel Reheem
Test carried by	Naha Samir
	* Mix . Fatma El Zahraa Fikry
	* H.Eng. Ahmed Said
	* Chem. Amr El Shafey
	* Dr. Abou El Fouah Abd El Hakem
Authorized by	Prof. Dr. Mostafa Zaki Mostafa
	* The Supervisor of ceramics, Polymer and Solid Matter Department.
	* Management Representative and Quality Assurance Manager.
Issue date	27/4/2021
Condition of Test & Issue	The test specimen was conditioned at 23 °C with a humidity of 60 % and the needed calibrations as well as balancing of the all used machines were always done .

شارع التحرير - الدقي - القاهرة


مباشر ٢٢٢٧٨٠٠٢
فاكس

داخلي ٩٤٧٤
٩٤٧٤

٢٢٢٧٧٤١٥ - ٢٢٢٧٧٤١٤
٢٢٢٧٧٤١٤ - ٢٢٢٧٧٤١٤



E-mail: nrc1302a@yahoo.com



NATIONAL RESEARCH CENTER
EL-DOKKI, CAIRO, EGYPT
Central Unit For Analysis And
Scientific Services (CUASS)
Material Test Lab.

المركز القومي للبحوث

القاهرة - جمهورية مصر العربية
وحدة التحليل والخدمات العلمية المركزية
معمل اختبار المواد



TO: iChem.EG construction chemistry

Dear Sir,

With correspondence to your request dated 20/4/2021 concerning the testing sample of iso-Flex PVC waterstops Q30. We would like to inform you that the all following needed tests were carried out which namely:

1- Tear strength test according to ASTM D624

We would like to inform you that the needed test was carried out taking into consideration the following conditions :

- 1- In all mechanical properties GALDABINI – QUASAR 600 – Made In Italy Universal Testing Machine was used This type has a self calibration , zero adjusting and automatic balance , which are done daily before testing or during testing this testing instrument is accompanied by a highly reliable system for evaluating the mechanical properties .
- 2- Measuring drum of sensitivity $\pm 0.01mm$ was used for dimensions evaluation
- 3- Weighing Balance with tolerance $\pm 0.0001 g$ was used in determining the weights .
- 4- All used Machinery and apparatuses were calibrated periodically.

The following table give the obtained results representing the sample delivered from your company .



Application Instructions

Equipment required:

- isoFlex PVC[®] jointing jig.
- electrically heated welding blade.
- Sharp knife.
- Wire brush.

Step 1

To trim the waterstop to length carefully measure the length of waterstop required and add 5 to 6mm to each mating end to allow for melting of the compound during the heat welding process. Clamp the end to be trimmed into one of the jointing jigs and cut to the required length using the side of the jig as a guide.

Step 2

Repeat this operation for the other mating end.

Clamp the two ends into their respective sides of the jointing jig, with approximately 10mm projecting and engage the guide rods.

Step 3

Plug in the welding blade and allow to warm up. Using a small offcut of waterstop, check that the blade reaches a temperature sufficient to melt the PVC.

When the blade is at melt temperature, place it on edge on the guide rods of the jig between the mating ends of the waterstop and press the waterstop firmly against either face of the blade.



isoFlex PVC®



Step 4

The PVC will start to melt in contact with the blade. Maintain the pressure against the blade until a 5mm diameter bead of molten PVC has formed on both sides all around the section.

When this has happened, pull the jig apart and lift away the blade with an upwards motion taking care to avoid too much displacement of the molten PVC bead. Turn off the blade.

Without delay, whilst the PVC is still molten, press the two mating ends together and hold firmly for 20 seconds or so until the joint has cooled and solidified.

Step 5

Unclamp the jig and carefully lift out the waterstop allowing it to cool thoroughly.

Do not flex the joint until cool. Once cool inspect for imperfections.



Step 6

To fix to the rebar simply loop wire through the fixing eyelets and twist using a pair of pliers.



This will leave the **isoFlex PVC®** Waterstop ready for your concrete pour.

isoFlex PVC[®]






Our Previous Submittals & Approvals

باسم

		هيدرون Hydr <small>Hydra-Flow Solutions for Building</small>
الإشغال العسكرية Project Name: راميل		
Material Submittal تقديم مواد / خامات		
Submittal No. رقم التقديم: TK20 1226-4	Rev. الاصدار: 1	Date تاريخ التقديم: 04/05/2024
Division: <input type="radio"/> GTR <input type="radio"/> ARCH <input type="radio"/> NEPA <input type="radio"/> ELEC <input type="radio"/> MECH <input type="radio"/> MAT <input type="radio"/> GTR		
Attachments: <input type="checkbox"/> Compliance Statement <input type="checkbox"/> Specs / BOD / Tastes <input type="checkbox"/> Test Certificate <input type="checkbox"/> Non-Ferrous Certificate <input type="checkbox"/> Test Certificate		
Name of the Product water stop عرض 24 سم بيمت 6 امير		
Specific Area of Application مكان الاستخدام		
Specification / Standards / References المواصفات / المعايير / المراجع		
Manufacturer (Name / Address / Phone) بلد التصنيع		
Country of Origin بلد التصنيع		
Supplier / Local Agent (Name / Address / Phone) شركة المتخصص		
Applicator / Installer (Name / Address / Phone) بلدان مقادير التركيب		
We declare that the above information has been confirmed and considered to be in full accordance with the contract documents / requirements.		
Contractor's Name اسم المقاول	Signature التوقيع	Date التاريخ
Contractor's Name اسم المقاول	Signature التوقيع	Date التاريخ
Received by Consultant استلام المقدم	Signature التوقيع	Date التاريخ
Approval Status حالة الموافقة	Approved As Noted Approved As Modified	
Consultant Rep. ممثل المقدم	Received by Contractor استلام المقدم	
22/15/2024		22/15/2024

1226-4
 1115-3623
 23 MAY 2024
 هيدرون Hydr

1226-4
 1115-3623
 23 MAY 2024
 هيدرون Hydr

																										
<p>مشروع إنشاء محطة نقل البواخر بالمدينة الإدارية الصنف مواد Material Submittal</p>																										
		رقم الطلب: 29-04-2021																								
		رقم الطلب: 11																								
<input type="checkbox"/> مائية	<input type="checkbox"/> كهربائية	<input type="checkbox"/> ميكانيكية																								
<input checked="" type="checkbox"/> أخرى																										
isoFlex PVC Water Stop System																										
isoFlex PVC Water Stop System - Standard V24																										
IC Chem LLC																										
رقم الطلب: 29-04-2021 رقم الطلب: 11																										
<input type="checkbox"/> نموذج		<input checked="" type="checkbox"/> حيا																								
<input type="checkbox"/> نموذج		<input checked="" type="checkbox"/> حيا																								
مدير المشروع: Mameen Al-Sayid مدير المشروع: Mameen Al-Sayid		مدير المشروع: Mameen Al-Sayid مدير المشروع: Mameen Al-Sayid																								
رقم الطلب: 29-04-2021																										
<p>1- تم فحص المنتج في الموقع والتأكد من مطابقته لملف المواصفات 2- Method statement تم فحصه والتأكد من مطابقته لملف المواصفات 3- تم فحص المنتج في الموقع والتأكد من مطابقته لملف المواصفات</p>																										
<input type="checkbox"/> OK	<input checked="" type="checkbox"/> OK مع ملاحظات	<input type="checkbox"/> NG																								
مدير المشروع: Mameen Al-Sayid توقيع: Mameen Al-Sayid التاريخ: 29-04-2021	مدير المشروع: Mameen Al-Sayid توقيع: Mameen Al-Sayid التاريخ: 29-04-2021	مدير المشروع: Mameen Al-Sayid توقيع: Mameen Al-Sayid التاريخ: 29-04-2021																								
<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>CODE</th> <th>STATUS OF APPROVAL</th> <th>NAME</th> <th>SIGN</th> </tr> </thead> <tbody> <tr> <td>A</td> <td>APPROVED</td> <td></td> <td></td> </tr> <tr> <td>B</td> <td>APPROVED WITH NOTES</td> <td></td> <td></td> </tr> <tr> <td>C</td> <td>RESUBMIT WITH NOTES</td> <td></td> <td></td> </tr> <tr> <td>D</td> <td>REJECTED</td> <td></td> <td></td> </tr> <tr> <td colspan="4" style="text-align: center;">DATE: 29-04-2021</td> </tr> </tbody> </table>			CODE	STATUS OF APPROVAL	NAME	SIGN	A	APPROVED			B	APPROVED WITH NOTES			C	RESUBMIT WITH NOTES			D	REJECTED			DATE: 29-04-2021			
CODE	STATUS OF APPROVAL	NAME	SIGN																							
A	APPROVED																									
B	APPROVED WITH NOTES																									
C	RESUBMIT WITH NOTES																									
D	REJECTED																									
DATE: 29-04-2021																										

شركة الحديد والصلب وشركة
الاصطناعية للأبواب والنوافذ

	رقم العمل: 000-000	نوع العمل: أعمال حديدية	تاريخ المشروع: 25/11/2006
	رقم الترخيص: [مخصص واصحاب المزايا]	الإصدار: [الرجوع]	تاريخ التقديم: 25/11/2006
		الموقع: [الرجوع]	وقت التقديم: 10:00
			وقت العمل: 18:00

المطلوب المخصصة :

تسليم تقرير نتائج إحصيات Water Stop من إنتاج شركة iChemEG

<table border="1" style="width: 100%; border-collapse: collapse;"> <tr><td>تاريخ الإصدار: 25/11/2006</td></tr> <tr><td>رقم الإصدار: 1666</td></tr> <tr><td>موقع العمل: [مخصص]</td></tr> <tr><td>اسم العميل: [مخصص]</td></tr> </table>	تاريخ الإصدار: 25/11/2006	رقم الإصدار: 1666	موقع العمل: [مخصص]	اسم العميل: [مخصص]	
تاريخ الإصدار: 25/11/2006					
رقم الإصدار: 1666					
موقع العمل: [مخصص]					
اسم العميل: [مخصص]					

التوقيع: [مخصص]

مهندس المخطوط مطلق	التوقيع: [مخصص]	تاريخ: 2006 / 8 / 20
مهندس المخطوط EM	التوقيع: [مخصص]	التاريخ: [مخصص]

مراجعة إلى:	مساعدة	مهندسين	ميكانيكا	كهرباء	G.C
-------------	--------	---------	----------	--------	-----

تعليق مهندس المخطط - 1

موافق

مطلوب <input checked="" type="checkbox"/>	مطلوب ملاحظات <input type="checkbox"/>	غير مطلوب <input type="checkbox"/>
مهندس الإشراف: [مخصص]	التوقيع: [مخصص]	تاريخ: 20 / 11
مهندس المخطوط: [مخصص]	التوقيع: [مخصص]	التاريخ: [مخصص]

Proj. No. : DABDM132	Employer:  Gulf General Contracting	Request No. OCE/DAU/506/HNB/CV/099
Engineer:  Gulf General Contracting	Contractor:  ORASCOM	Date 16 / 12 / 2010

Submission for Approval of Materials

1. Material description (one item only on this form) :
 Cold applied bitumen emulsion for foundation waterproofing (Isoflex PVC-Standard 514)


Area of application : All Concrete Elements
 Drawing ref. : _____ S.O.Q. Ref. No. : _____
 Specification Ref. : SP155 (CLAUSE X.1) Standards : _____
 Attach all relevant technical literature marked to identify relevant description, current Test Certificates, samples as appropriate.

2. Manufacturer / supplier
 Company Name : ORASCOM
 Address : 24 Mohamed Moustafa Road Elkhayma/Dokki/El-Dokki/El-Dokki/El-Dokki
 Local Agent : 200

3. Delivery :
 Country of origin : _____
 Locality : Locally Manufactured Overseas

Delivery : To working / total duration : 15 days
 Estimated time of arrival on site : 2 days

Program : Date material required on site : 24 Jan. 2011
 Latest date for order : 10 Feb 2011



We certify that the above submitted items have been reviewed in detail and are correct and in strict conformity with the contract drawings and specifications except as otherwise stated; also that the material sources indicated above have been reviewed in detail and that they will supply the submitted items in conformity with the above and deliver same timely.

Submitted by : Sami M. El-Hadi Signature: [Signature]




4. Engineer's Representative comments: <i>Material accepted.</i> <i>Following specs & General notes regarding Lead wires.</i>	<input type="checkbox"/> Approved
	<input checked="" type="checkbox"/> Approved as noted
	<input type="checkbox"/> Review and re-submit
	<input type="checkbox"/> Rejected
	<input type="checkbox"/> Sample required
	<input type="checkbox"/> Tests required
	<input type="checkbox"/> Additional information required
	<input type="checkbox"/> Manufacturer's guarantee required
Signature: <u>[Signature]</u> Date: 16 / 12 / 2010	

Approved shall not release Contractor of his liabilities under the Contract or constitute authorization of any release or Contract Termination.

		SHAKER	
HASSAN ALLAM		SHAKER	
بيانات العميل (معلومات الشركة)			
رقم العميل	0	اسم العميل	PRIME/030-BAO-0061 041
التاريخ		20-12-2020	الوقت
الوصف (معلومات المنتج)			
isoFlex PVC Window Sash والقضبان البلاستيكية موزونة شركة اليمام			
معلومات المنتج (معلومات المنتج)			
<input type="checkbox"/> تصنيع	<input type="checkbox"/> تعبئة	<input type="checkbox"/> شحن	<input type="checkbox"/> تسليم
<input type="checkbox"/> تركيب	<input type="checkbox"/> اختبار	<input type="checkbox"/> فحص	<input type="checkbox"/> مراجعة
<input type="checkbox"/> مراقبة	<input type="checkbox"/> تسليم	<input type="checkbox"/> تصحيح	<input type="checkbox"/> إغلاق
معلومات العميل (معلومات العميل)			
اسم العميل			
العنوان			
الرقم			
الحي			
البلد			
الهاتف			
البريد الإلكتروني			
موقع العميل			
معلومات العميل (معلومات العميل)			
اسم العميل			
العنوان			
الرقم			
الحي			
البلد			
الهاتف			
البريد الإلكتروني			
موقع العميل			
معلومات العميل (معلومات العميل)			
اسم العميل			
العنوان			
الرقم			
الحي			
البلد			
الهاتف			
البريد الإلكتروني			
موقع العميل			

RECEIVED
25 DEC 2020
HAC

أولادنا في البيت والجميع في البيت
هذا هو البيت الذي نعيش فيه
وكلنا في البيت الذي نعيش فيه

مكتب المقاولات العربى الهندسية 	وزارة الدفاع الهيئة الهندسية للقوات المسلحة إدارة المهندسين المدنيين	شركة أيدام مصر للطرق و القناري IDG شركة أيدام مصر للطرق و القناري	
PROJECT : REGIONAL RING ROAD TUNNELS (R&C)			
DOCUMENT SUBMITTAL			
FOR INFORMATION AND RECORD	<input type="checkbox"/>	FOR APPROVAL	<input checked="" type="checkbox"/>
DATE:	30 May 2024	SUBMITTAL NO.	01
Drawn:	Ahmed Elshay	Signature:	
Title:	T.O.M	Signature:	
CC:	Owner Engineer	Signature:	
EXHIBIT TITLE :			
iChemDG - Products			
Design Remarks :			
1- Light Q30		2- Standard SM32	
3- Light L20		4- Standard V24	
5- Standard W20		6- IsoFlex (PVC) - Water Stop	
Consultant Comments :			
			
Approved	<input checked="" type="checkbox"/>	Approved by (Initial)	<input type="checkbox"/>
Review & Resubmit	<input type="checkbox"/>	Not Approved	<input type="checkbox"/>
Consultant Engineer :	Owner Engineer :		
Name:	Name:		

Submittal for approval of materials

Date: 05/22/24
Request No: 245-2024-00-013-Rev. 01

Project: 245-0001
245-0001/Construction Buildings on Farm 146 to 166

Employer: **Engineer:** dar **Constructor:** dar

1. Material description (see also only on this form)

Material: Isoflex (PVC) - Water Stop PVC Water Stop
 Area of application: Tanks
 Drawing ref: ISO flex Section and Details (ISOflex)_Rev 02
 Manufacturer: ISOflex
 Manufacturer's technical document: Technical data sheet
 Approval: [Signature]

F. Material Supplier:
 Company name: ISOflex
 Address:
 Local agent:

G. Delivery:
 Supplier: ISOflex
 Locally Manufactured Imported
 Delivery: 2x weekly for duration
 Estimated time of arrival on site:

We certify that the material described in this submittal complies with the contract drawings and specifications. I warrant that the material is of the quality, quantity and source indicated above and will comply with the contract drawings and specifications.

Submitted by: [Signature] **Agreement:**

<input checked="" type="checkbox"/> Approved
<input checked="" type="checkbox"/> Approved with notes
<input type="checkbox"/> Rejected
<input type="checkbox"/> Rejected - resubmit
<input type="checkbox"/> Rejected - resubmit
<input type="checkbox"/> Tests required
<input type="checkbox"/> Additional information
<input type="checkbox"/> Rejected - resubmit
<input checked="" type="checkbox"/> Manufacturer's guarantee


*Submit test report
 - size and type to be as per drawing*

for 1A Remodel on 8/12/24

Approved on behalf of Employer (see header) and the Constructor (submitter) at this office in United States

[Signature]
 dar

Submittal for approval of materials



Date: 27/09/17
Request no. RMR/INT/ESC/2017/001

Project no. & title: FRIEDLANDER MINISTRIES' COMPLEX (Area 3A & 4A)

Employer 	Engineer dar	Contractor
--------------	------------------------	----------------

1. Material description (use item only on this form):
 Article title (include P/N, - Model, Size):

Area of application: Water Tank
 Drawing ref.: _____ B.O.D. ref. no.: _____
 Specification Ref.: _____ Standard: _____
 Attach all relevant technical literature marked to identify relevant description, current Test Certificate, samples and appearance.

2. Manufacturer / Supplier:
 Company Name: Chowdh
 Address: _____
 Local agent: _____

3. Delivery:
 Country of origin: _____
 Availability: Locally Manufactured Overseas

Delivery:	Estimated time duration:			
	Estimated time of arrival at site:			
Program:	Date material required on site:			
	Latest date for order:			

We certify that the above-submitted items have been reviewed in detail and are correct and in strict conformity with the contract drawings and specifications except as otherwise stated, also that the material sources indicated above have been reviewed in detail and that they will comply with the submittals in conformity with the above and deliver same timely.

Submitted by: Mustafa Youssef Signature: _____
 Authority: Contract (Design) project manager Position: For


4. Engineer's representative comments:

Area Use 2.5 cm with minimum
- Submit test report
- Size, shape as per drawing

Remarks: Area Date: 2019/11/7

<input type="checkbox"/> Approved	<input checked="" type="checkbox"/> Approved as noted
<input type="checkbox"/> Rejected	<input type="checkbox"/> Pending
<input type="checkbox"/> Resubmit	<input type="checkbox"/> Sample required
<input type="checkbox"/> Test required	<input type="checkbox"/> Additional information
<input type="checkbox"/> Rejected	<input type="checkbox"/> Manufacturer's guarantee

FORM-0300001 Rev 1



dar

161

HASSAN ALLAM		SHAKER	
اتفاق الخدمة بالعاصمة الادارية (NCT)		نموذج اعتماد مستندات	
التاريخ: 16-10-2018	الاصدار: 0	النموذج: P023/CC/TR-HAC-CON-522	
المستلم: المجموعة الهندسية (شاكرا)		الموضوع: اعتماد مادة مانع تسرب 1- الفاصل الاتشاني Standard O25 2- فاصل التمدد Standard O30 من مورد iChemEG	
طبيعة العمل:			
<input type="checkbox"/> المكتب الفني	<input type="checkbox"/> امن وسلامة	<input checked="" type="checkbox"/> جوده	<input type="checkbox"/> مساحة
عام			
غرض تقديم المستندات:			
<input type="checkbox"/> اعتماد المنفذ	<input type="checkbox"/> للاستفسار	<input type="checkbox"/> للعلم	<input checked="" type="checkbox"/> للتصميم
غرض تقديم اللوحات:			
<input type="checkbox"/> لتصميم	<input type="checkbox"/> لرسومات التنفيذ	<input type="checkbox"/> اعتماد منفذ	<input type="checkbox"/> نوتة حسابية
مرفق طيه:			
1- عدد 2 Data Sheet			
2 عدد 2 عينة			
SHAKER CONSULTANCY GROUP MAST			
الختم:	توقيع مدير الجوده:	توقيع مدير المكتب الفني:	توقيع مدير المشروع:
ملاحظات الاستشاري :			
قرار الاعتماد:			
<input checked="" type="checkbox"/> B	معتمد بوجود ملاحظات	<input type="checkbox"/> A	معتمد بدون ملاحظات
<input type="checkbox"/> D	للعلم	<input type="checkbox"/> C	مرفوض
التاريخ :		اسم :	
استلام المقاول :		التوقيع :	

