

Description


The **i110**® roof expansion joint system accomodates multi-directional seismic movement and is installed with a 2x up stand mount.

Key Features

- · Install Condition: Roof/Roof, Roof/Wall.
- **Joint width:** Manufactured according to site requirements.
- · Optional fire rated.
- Seamlessly integrates with coordinating Wall system.
- Applicable for existing conditions, additions and new construction.
- · Mill finish aluminum.

Materials

Aluminum: Alloy types of 6061-T6, 6063-T6, 6005A, or 5052-H32 sheet goods.



Application Instructions

Installaion: Joint systems: Install in accordance with manufacturer's instructions.

Align work plumb, level and flush with adjacent surfaces. Mechanically anchor to substrate. Allowances should be made where actual structural gap at time of installation varies from nominal design gap. No shimming of frames is permitted. Coordinate with work of other Sections.

If concrete blockouts (rebates) are required, ensure continuous support equal to surrounding substrate structural values.

Fire Rated Assemblies: Where required, install to manufacturer's instructions.

Moisture Barrier: Where required, install to manufacturer's instructions.





Protect: the completed Expansion Control system work from damage during construction. Damage protection includes surface abrasion and overloading of coverplate by materials handling equipment and construction waste/debris. Protection from environmental factors required throughout installation process until Project Closeout. Protection includes but is not limited to rain events, moisture protection, exposure to temperature fluctuations or direct sunlight for temperature sensitive product offerings.

Store

Store components in original containers in a clean, dry location. Ensure temperature or moisture sensitive components are stored in a tempered location.


Contractor to provide temporary protective covers on all installed finished surfaces. Protection is required to guard against both surface abrasions as well as overloading of horizontal deck components by construction traffic.

Movement ± 50%


		W	H1 H2		S	Movement +/-		L		
Application	System	Joint Width	Frame Height 1	Height 2	Sightline	Horizontal	Vertical	Load		
		mm	mm	mm	mm	mm	mm	Kn		
Roof to Roof	Manufactured according to site requirements									
Roof to Wall	Manufactured according to site requirements									



Series i110 - Roof to Roof




Series i110 C - Roof to Wall





Series i110-FireStop S30 Options





Our Previous Submittals & Approvals



MUST CONSTRUCTION COMPANY		WIND THE PARTY OF		HA Engresenio Consultino Louist apl will					
		عتماد مواد							
	M	laterial Appro	val Re		6/05/2024	1	التاريخ :-		
26/05/2024 MCC-MUST-MAR-AR-093-00									
MCC-MUS1-MAK-AK-093-00 چامعة مصر للطوم والتكنولوجيا									
			مو اصفات فنية			رسومات تشغيل			
	اخري / Other	☐ As Built Dwg		Specs		work shop	200000		
ر د	الشركة / المو	المرفقات :		كهرباء	معدارى	انشانی			
ICH	IEM	عبنة + DATA SHEET			V		نوعية الاعمال		
	ICHEM a	نماد عينات فواصل شرك الشركة : ICHEM	طلب اعت				الموضوع		
نتيجــة القحص	الوصف / البيان (OUT COING) نتيجة القد								
(B) 1424 (LAND SCABE)									
(فاصل الحوانط + الاسقف الجراجات) 1870 (B)									
(B) IFLEX CSW (فاصل الجراجات)									
(B) 1110 (about hudes)									
				le de la companya de	IN C	16120.24	5		
	MUST CONSTI	RUCTION COM	IPANY	7	al Son	Struction C	Contractor/المقاول/		
(Mury)	مدير المشروع/ المقاول الاسم/Name : م مدير المشروع/ المقاول الاسم/Name : م محسم فؤاد : Name/ التوقيع/Signature : كناب المسلام التوقيع/Project Manager : كناب المسلام : Signature : كناب المسلام : Signature : كناب المسلام : كناب المسل								
		حص / Result	نتيجـــة الف						
	Evaluati	Date / تاريخ الاستلام							
مرفوض ا	بعاد التقديم / Resubmit	معتمد بشروط/	معتمد/		:Receive		: Receiver / المسئلم		
Rejected D	C	Approved as noted Approved B A D/							
م المانية المانية المانية	النخارية لسريدا النخارية لسريدا س لخرصه الحاد دن براجهون س	ع در عبد المقائد والعاكم والعالم الما	slive)	Baking	Pood Pood	لمشربه م جا لمراجع ج مراعات مات روداد محمدل لمعا	is ancied		
	لاسم/Name : كلا	مدير المشروع	~	- 1	. ': Signa	الاسم/Vanne الترقيع/ture التاريخ/Date	الإستشاري Consultant		





i110 Submittal - January 2025, Version 1.2.2



